

Name of Work: Fabrication & Supplying of Open Web Steel Girders of span size 3X45.7m with welded / riveted fabrication as per approved drawings for bridge on Dharam – Qazigund Section for bridge no.147 in Zone-IV (from Km 151.824 to Km 151.968) of Udhampur-Srinagar-Baramulla Rail-Link Project.

SL. No.	Description	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1.	<p>Fabrication of Open Web Steel Girders with footpath and trolley refuse complete with contractors own steel conforming to Fe 410C of IS-2062 including material and labour as per approved Railway drawings & RDSO specifications as described in tender documents and codal provisions including metallising / epoxy painting complete as per relevant clause of special conditions of contract. The fabrication cost includes all the types of battens, lacings, ties, stiffeners, packings, diaphragm, T&G bolts, steel drifts, shop welds, shop rivets, templates, jigs, fixtures, back up supports, accessories etc. and marking each member for site identification known as “shipping marks”. The job includes fabrication of steel girders with surface preparation, metal spraying, first and second coat of primer and first coat of finishing in case of primer and first coast of finishing in case of metalizing and surface preparation, all coats of primer and first finishing coat in case of epoxy painting.</p> <p>Included with</p> <p>Transportation of above material components from fabrication yard to site, including loading, transportation, unloading and with due care & safe guard as described in the specification to the satisfaction of Engineer –in-charge.</p>	MT	414		
	TOTAL				